

Next steps for Lea Valley main line

Jonathan
Roberts, JRC
7 February 2012



LSE RUS, IIP and beyond

- **Option C2a £35m+ = Brimsdown siding**
- **Option C2b £232m+ = partial 3 / 4 track**
- **Option C2a in NwR Initial Industry Plan**
- **Early modelling shows C2a doesn't work, while C2b not full outputs – and not affordable**
- **What are do-able interim options meeting stakeholder objectives within affordability?**

Core outputs – Main rail options

- **STAR = Stratford- Tottenham – Angel Road**
- STAR 1 = 2 tph extra Stratford-Tott.-Angel Rd
= 4 tph Stratford-Tott. + 2tph > AR + poss ML
- STAR 2 = 2 tph extra Stratford-Tott. = 4 tph
+ separate 4 tph Tottenham Hale-Angel Road

Option costings

- **STAR 2 = transport+development objectives**
 - CAPEX (TfL £ basis): £21m ST-TH,
£39.8m TH-AR = £60.8m
 - OPEX (inc ORR RAB): £2.8m ST-TH,
£2.8m TH-AR = £5.6m
- **STAR 1 = transport-led, combined service**
 - CAPEX (TfL £ basis): £52.4m
 - OPEX (inc ORR RAB): £4.5m



Operating costs

	STAR 1		STAR 2	
	ST-TH		TH-AR	
	only		only	
		OPEX		
	£m		£m	
ST-TH miles	0.9		0.4	TH-AR miles
2 train lease	1.0		0.5	1 train lease
ORR £ RAB	1.0		1.9	ORR £ RAB
	2.8		2.8	
combined cost £4.5m (-1 train, fewer miles to AR)				



Next steps

- **Work on revenue baselines and projections**
- **Work on core infrastructure costs**
- **Work on gaps in capex / opex vs projected income**